



RCC Design Future? Results from LTRC's Accelerated Loading Facility

Tyson Rupnow, Ph.D., P.E.
Zhong Wu, Ph.D., P.E.

LTRC Project 12-7P



April 26, 2016

Spring TTCC/NCC Meeting, Columbus, OH

Outline

- Background
- Objectives
- Field construction results
- Load test results
- Conclusions
- Implementation efforts
- Questions



Why interested in RCC?



Background

- RCC for roadways started in the mid-1980's
- Successful RCC projects include:
 - U.S. 78 near Aiken, SC
 - 10" RCC – 1 mile 4 lane section completed in 2009
 - 2012 Arkansas completed a section in the Fayetteville Shale Play Area
 - 7" RCC over a reconstructed base course
 - 8" RCC placed as an overlay



Objectives of the Study

- (1) to determine the structural performance with failure mechanism and load carrying capacity of **thin RCC** surfaced pavements
- (2) to determine the applicability of using a **thin RCC** surfaced pavement structure (with cement treated or stabilized base) as a design option for low- and high-volume pavement design in Louisiana



Lab Materials and Test Methods

- Materials
 - No. 67 crushed limestone
 - Manufactured sand
 - Type I portland cement
- Test methods
 - ASTM C1557 Modified Proctor
 - ASTM C1435 for cylinders
 - ASTM C39
 - ASTM C6938 and ASTM C1040




Laboratory Mixtures

- 350, 400, 450, and 500 PCY mixtures
- Tested for density first (Modified Proctor)
- Then tested for strength



Mixture Results - Strength



Mixture Proportion

Material	Quantity (pcy)
Cement	450
Coarse Aggregate	1521
Fine Aggregate	2017
Water	154



Constructed Sections



8 " RCC
12 "Cement Treated Base
Existing Subgrade

Section 1

6 " RCC
12 "Cement Treated Base
Existing Subgrade

Section 2

4"RCC
12 "Cement Treated Base
Existing Subgrade

Section 3

8 " RCC
8.5" Soil Cement Base
10" Cement Treated Subgrade
Existing Subgrade

Section 4

6 " RCC
8.5" Soil Cement Base
10" Cement Treated Subgrade
Existing Subgrade

Section 5

4"RCC
8.5 "Soil Cement Base
10" Cement Treated Subgrade
Existing Subgrade

Section 6



Pictures




Section 3



Section 6



Section 2



Section 5



Section 1



Section 4



FWD Backcalculated Layer Moduli



8"RCC+12CT

$E_{RCC}=3587\text{ksi}$
 $E_{base}=258\text{ksi}$
 $E_{sub}=27\text{ksi}$

Section 1

6"RCC+12CT

$E_{RCC}=2361\text{ksi}$
 $E_{base}=181\text{ksi}$
 $E_{sub}=24\text{ksi}$

Section 2

4"RCC+12CT

$E_{RCC}=2904\text{ksi}$
 $E_{base}=139\text{ksi}$
 $E_{sub}=22\text{ksi}$

Section 3

8"RCC+8.5SC

$E_{RCC}=3767\text{ksi}$
 $E_{base}=418\text{ksi}$
 $E_{sub}=31\text{ksi}$

Section 4

6"RCC+8.5SC

$E_{RCC}=3763\text{ksi}$
 $E_{base}=352\text{ksi}$
 $E_{sub}=28\text{ksi}$

Section 5

4"RCC+8.5SC

$E_{RCC}=4384\text{ksi}$
 $E_{base}=305\text{ksi}$
 $E_{sub}=26\text{ksi}$

Section 6

Section 1,2 & 3

Section 4, 5 & 6

Those backcalculated results consistent with FWD deflections obtained from individual layers

Field Results

- Density slightly lower in the bottom depth
- Strengths at 55 days of age
 - Lane 1 – 5192 psi
 - Lane 2 – 4422 psi
 - Due to lower densities

Section Number	Thickness (in)
1	9.65
2	6.05
3	4.90
4	8.01
5	6.36
6	4.10




Accelerated Pavement Testing - ATLaS30



Dual-tire load, 130psi
Load: up to 30 kips
Speed: 4~6 mph
Bi-directional loading
Effective length: 42-ft
About 10,000 passes/day



Accelerated Loading Testing




- Started on **Section 4**


8" RCC
8.5" Soli Cement Base
10" Cement Treated Subgrade
Existing Subgrade

- Roughly 78,000 reps. for each load level,


9,000 lb




16,000 lb



20,000 lb



22,000 lb





25,000 lb





Instrumentation Response

- Typical stress and strain measured at the bottom of RCC slabs with different thickness under APT loading




- Typical stress and strain measured at the bottom of RCC slabs over different base support under APT loading



Distress Observed (8+8.5RCC) – Section 4

- Approximately after 392,500 load repetition (11.28 million equivalent ESALs), no significant damage was observed
- Due to the high load repetitions received on section 6+8.5RCC to fatigue failure, the test was discontinued

392,500 Passes




Current Pavement Condition

Distress Observed (6+8.5RCC) – Section 5

- Visual Distresses
- Longitudinal cracks were observed along the wheel path and at the edge of the tire print
- Pumping action was observed through cracks and joints
- 87.4 million ESALs to failure
- ***1.9 million ESALs predicted***

1.75 million Passes



Pavement Condition at the end of testing

Distress Observed (4+8.5RCC) – Section 6

- Visual Distresses
- Longitudinal cracks were observed along the wheel path and at the middle of the tire print
- Pumping action was observed through the cracks and joints
- 19.2 million ESALs to failure
- ***0.7 million ESALs predicted***

706,500 Passes




**Pavement Condition at the
end of testing**

Distress Observed (4+12RCC) – Section 3

- Due to relatively weaker support, an early longitudinal crack was observed after 55,000 passes under 9 loading
- About 3 million ESALs to failure
- *Predicted 0.7 million ESALs to failure*

196,000 Passes



Longitudinal crack along the wheel path

Distress Observed (6+12RCC) – Section 2


- Longitudinal cracks
- Pumping and Local failure
- About 19 million ESALs to failure
- *Predicted 1.9 million*

637,000 Passes




Crack Mapping on (6+8.5RCC) – Section 5

□ Crack Mapping




Crack Mapping on (4+8.5RCC) – Section 6

□ Crack Mapping




Crack Mapping on (6+12RCC) – Section 2



Comparison of Cracking Pattern of Failed RCC Sections

- Crack initiated at the weakest subgrade location
- Cracking pattern for thicker section was much wider than the thinner section
- Uniform subgrade resulted in a final cracking failure covering the entire loading area for 6+8.5RCC & 4+12RCC



Construction Cost Analysis

- 13-ft wide , 1 mile length
 - RCC = \$198,082
 - HMA = \$311,169
- Typical 2-lane, 10 mile long project
 - 5-in RCC vs. 7-in HMA
 - Total cost savings up to \$2,261,740



Summary

- ❑ Except two 8” RCC test sections, the best performer is (6”RCC + 8.5” soil cement) section, with
 - ❑ Rideable surface and relatively low IRI;
 - ❑ Outstanding load carrying capacity, est. ESALs = 87.4 M;
 - ❑ Potential to be used for heavy-loaded, medium speed pavements;
- ❑ Sections (4”RCC+8.5” soil cement) and (6”RCC+12” cement treated) also performed very well
 - ❑ Both can carry large amounts of heavy traffic (half axle >20kips); Est. ESALs > 15 M
 - ❑ Surface IRI to be controlled during the construction
 - ❑ Potential to be used for low-volume roads with heavy truck traffic.



Summary (cont.)

- ❑ Four RCC sections failed under fatigue cracking. The observed fatigue cracks were initiated first either in the middle or at the edge of the tire print along a longitudinal direction;
- ❑ The width of fatigue cracking pattern was found much wider for 6-in RCC sections (e.g. 6+8.5RCC) than that for 4-in. RCC sections
- ❑ RCC-Pave fatigue models were found not suitable for the fatigue life prediction of thin RCC sections evaluated.
- ❑ Two preliminary fatigue models for thin RCC pavement fatigue analysis have been developed



RCC Implementation

- The ATLaS30 loading results generally indicate that
 - a thin-RCC over soil cement pavement structure has a superior load carrying performance
 - Recommendation to select and build several field RCC test sections on those Louisiana highways where the pavements are often encountered by heavy truck loading
 - To validate the APT performance and provide further implementation guidelines
 - *Will not test the 8-inch sections to failure!*



Acknowledgements

- The construction of RCC test lanes was a joint effort between LTRC and its concrete industry partners:
 - CAAL was instrumental in arranging industry support through donations of manpower and materials for this project;
 - Gilcrest Contractors provided the manpower and equipment to construct the subgrade and base courses;
 - Holcim and LaFarge provided cement
 - Vulcan Materials provided aggregate
 - Rollcon in Houston, TX paved the test lanes; and
 - Cemex of Arizona setup and operated pugmill

