

U.S. 18 – 4" PCC Unbonded Overlay

2-Lane Roadway Overlayed Under Traffic
Chickasaw / Fayette County, Iowa

National Concrete Consortium
Rapid City, South Dakota
September 13, 2011



By: Dale S Harrington P.E - Representing the CP Tech Center .



Iowa Department of Transportation

Highway Division

Plans of Proposed Improvement on the Primary Road System - Chickasaw / Fayette County 4" PCC UNBONDED OVERLAY

US 18 From Fredericksburg E. to West Union

Refer to the Proposal Form for list of applicable specifications.
 Refer to the General Notes for list of applicable specifications.

MILEAGE SUMMARY			
Dist.	Location	Lin. Ft.	Miles
1	Sta. 240+00.0 - Sta. 622+02.85	21622.85	6.62
	Eq. Sta. 622+02.85 = Sta. 0+00		
	Sta. 0+00 - Sta. 344+08.43	34408.43	6.52
	Eq. Sta. 344+08.43 = Sta. 344+15.27		
	Sta. 344+15.27 - Sta. 703+73.24	36957.97	6.89
	Inst. Bridge Sta. 344+30	-100	-0.02
	Inst. Bridge Sta. 418+23	-140	-0.03
	Inst. Bridge Sta. 61+19	-22	-0.0
	Inst. Bridge Sta. 242+35	-47	-0.01
	Totals		98248.65

PROJECT IDENTIFICATION NUMBER	06-19-018-010
PROJECT NUMBER	NW88-018-7050-3H-27
R.O.M. PROJECT NUMBER	

ROADWAY DESIGN

I hereby certify that the engineering document(s) prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

Robert A. Skogenboe
 Robert A. Skogenboe
 License No. 18437
 State of Iowa
 My license renewal date is December 31, 2011.

Pages or sheets covered by this seal: A-1, B-1, C-1, D-1, E-1, F-1, G-1, H-1, I-1, J-1, K-1, L-1, M-1, N-1, O-1, P-1, Q-1, R-1, S-1, T-1, U-1, V-1, W-1, X-1, Y-1, Z-1.

FINAL BID COPY 10/19/10

- Late Start Date - April 14, 2011
- Number of working days - 120
- Number of Bidders - 6
- Bid range \$8.48 million to 10.51 million
- Prime Contractor - Manatts, Inc., Brooklyn, Iowa

DESIGN TEAM LEADER

Dave Skogenboe
 515-239-1612
 800 Lincoln Way
 Ames, Iowa 50010

CHICKASAW CO.		FAYETTE CO.	
06-20-02	20-4	06-20-02	20-4
DESIGN DATA RURAL		DESIGN DATA RURAL	
2008 AADT	1800 V.F.D.	2008 AADT	2000 V.F.D.
20 AADT	V.F.D.	20 AADT	V.F.D.
20 DRY	V.F.H.	20 DRY	V.F.H.
TRUCKS	22 %	TRUCKS	13 %
Total		Total	
Design DSALs		Design DSALs	

PROJECT OBJECTIVE DESCRIPTION


- a. Place unbonded PCC overlay while staging traffic through the project with the aid of a pilot car.
- b. All preliminary work is to be included in stages one to two prior to overlay paving.
- c. Transition pavement is required at the BOP, EOP and four bridge sites.
- d. Microsurfacing to be removed on the west portion (BOP to County W-14 by milling.
- e. Four paved side roads are affected by the overlay work.


SIGNIFICANT CONTRACT ITEMS

- a. Patches by count - 651 PCC patches, 4-30 foot in length
- b. Longitudinal subdrains - 113 locations with lengths of 250-540 feet
- c. Temporary barrier rail - 6 locations (BOP, 4 bridges and EOP)
- d. Temporary traffic signals, bridge approach and railing rehabilitation - 4 bridge locations
- e. Shoulder improvement and drainage work - 223 locations

MAJOR CONTRACT QUANTITIES (TOTAL CONTRACT ITEMS)

a. Slipform 9.5 inch class 3 durability pavement	6,623 sy
b. Concrete Furnish	48,605 cy
c. Concrete Place	350,267 sy
d. Surface preparation	94,681 sy
e. Granular shoulder material, placed	67,741 tons
f. Shoulder strengthening (PCC or HMA)	3,993 sy
g. Patches full depth repair	4,337 sy
h. Patches by count	651 each
i. Class 13 widening excavation	12,894 sy
j. Pavement Scarification	169,982 sy
k. Granular surfacing	2055 tons
l. Longitudinal subdrain	48,422 LF
m. Pavement removal	23,858 sy
n. Temporary barrier rail	5,720 LF
o. Longitudinal joint repair	10,920 LF





- PCC Overlay
- ① Rumble slope to be 2%
 - ② Refer to additional listing of approved curves and Scarfed Road Plan for additional requirements through representative curves.
 - ③ Shoulder is assumed to be 1" lower than existing pavement. Class II finish shall be used.
 - ④ 100% inside 24" side curbs are present.
 - ⑤ Provide a vertical edge. Incident to Class II Scarvation.
 - ⑥ No side per station.


* Sta. 632+02.85 to Sta. 640.00
 ** Sta. 344+05.43 to Sta. 344+35.27 MI

Location		Overlay Details										Remarks
Road Description	Station to Station	A	B	C	D	E	F	G	H	I	J	
US 28	344+02.85	4	1	2	3	4	5	6	7	8	9	
US 28	344+05.43	4	1	2	3	4	5	6	7	8	9	
US 28	344+08.00	4	1	2	3	4	5	6	7	8	9	
US 28	344+10.57	4	1	2	3	4	5	6	7	8	9	
US 28	344+13.14	4	1	2	3	4	5	6	7	8	9	
US 28	344+15.71	4	1	2	3	4	5	6	7	8	9	
US 28	344+18.28	4	1	2	3	4	5	6	7	8	9	
US 28	344+20.85	4	1	2	3	4	5	6	7	8	9	
US 28	344+23.42	4	1	2	3	4	5	6	7	8	9	

TYPICAL CROSS SECTION
 PCC OVERLAY WITH BASE WIDENING

Posted Speed Limit	Design Speed (MPH)
15 to 20	15
25 to 35	25
40 to 50	35

* Based on design speed as set on side roads and intersections.



- ⑤ PCC Overlay
- ⑥ Milling

Location	L1	L2	S	T1	T2
344+03	100	200	4	7	1.5
344+05	100	200	4	7	1.5

DETAILS OF TRANSITION
 FROM PCC OVERLAY OVER
 EXISTING HMA TO OVERLAY
 OVER EXISTING PCC PAVEMENT



PROJECT STAGING

STAGE I (CHANGE IN PATCHING TIMING)

- Maintain through traffic at all times.
- Patch between BOP and EOP(entire length of project)
- Construct subdrains, culvert work, foreslope flattening, ditch reshaping and erosion control from BOP to EOP

STAGE II

- Maintain through traffic at all times and use TBR/signals where necessary.
- Place shoulder strengthening, TBR and signals, attenuators, and flood lights at four bridge locations and EOP.
- Reconstruct bridge approaches, ½ at a time and place temporary HMA wedges

STAGE III

- Maintain through traffic at all times from W-14 to EOP with pilot car.
- Close county roads as required to place PCC overlay
- Prepare base for overlay between W-14 and EOP.
- Place PCC overlay one lane at a time, shoulder, mark lines as noted and open to traffic between W-14 and EOP.

STAGE IV

- Maintain through traffic at all times from BOP to W-14 with pilot car.
- Mill microsurfacing between BOP and W-14.


STAGE V

- Maintain through traffic at all times from BOP to W-14 with pilot car.
- Close Co Road V-68 and reconstruct tie in areas
- Close other county roads as required to place PCC overlay.
- Place PCC overlay one lane at a time, shoulder, mark lines as noted and open to traffic between BOP and W-14.

STAGE VI

- Maintain through traffic on US 18 at all times.
- Construct right turn lanes at V-68 and W-14.
- Remove and replace paved entrances
- Place rumble strips from BOP to EOP

PAVING STAGING



PAVING SEQUENCE EAST TO WEST

Non-Mainline Paving Days = 3,6,7,10,13,16,19,20,23,26,29,31,32,35

SHOULDER PAVING


SAFETY WEDGE

0.25 MILE





PAVING WITH MACHINE CONTROL
WITHOUT CENTERLINE STRING
LINE



STRINGLESS MACHINE CONTROL

Thank You

**National Concrete Pavement
Technology Center**

