



Statewide Teamwork

Missouri's Safe & Sound Project

Ken Warbritton, MoDOT



Overview



- Brief History
- Team Organization and Communications
- Results
- Public Acceptance
- Lessons Learned



Contract Models

- Design-Build-Finance-Maintain (DBFM)
- Design-Build
- Modified Design-Bid-Build




Project Timeline

- ❑ Oct. 2006 Project announced as DBFM
- ❑ Sep. 2008 DBFM model viable, but unaffordable ... Credit Crisis split procurement into DB (554) and MDBB (248)
- ❑ Apr. 2009 First Bridge Complete (MDBB)
- ❑ May 2009 KTU Constructors selected as Design-Builder
- ❑ Dec. 2009 First 4 DB Bridges Complete
- ❑ May 2010 DB Design Complete
- ❑ Nov. 2012 Final Bridge Completed



CONDITION 3 AND 4 STATE STRUCTURES

10,249
bridges on
MoDOT system at
start of program.



1,093 were Condition 3
(serious) or Condition 4 (poor)

Why Do a State-wide Bridge Project?


Bridge Deterioration



Project Goals

1. Deliver good bridges at a great value.
2. Minimize public inconvenience through increased construction speed & flexible schedule.
3. Complete construction by Dec. 31, 2013.

Safe & Sound Partners



Regional Offices

NW Region

2011 Office: St. Joseph

KTU Reg. Sup.

Dave Lehr

MoDOT Reg. Field Eng.

Troy Slagle

KC Region


2011 Office: Lee's Summit

KTU Reg. Sup.

Cory Gapstur

MoDOT Reg. Field Eng.

Mary Miller



SW Region

2011 Office: Bolivar

KTU Reg. Sup.

Keith Hoff

MoDOT Reg. Field Eng.

Jim Conley

NE Region

2011 Office: Columbia & Kirksville

KTU Reg. Sup.

Steve Kullman

MoDOT Reg. Field Eng.

Preston Kramer

SE Region

2011 Office: Benton

KTU Reg. Sup.

Brian Cruickshank

MoDOT Reg. Field Eng.

Andy Meyer



KTU CONSTRUCTORS

Northwest Region

6,049 SQ Miles
52 Single Span Precast Concrete
18 Two Span Precast Concrete
38 Three Span Precast Concrete
1 Cast in Place Slab/Box Culvert
2 Steel Beam W/ Concrete Deck
111 Total Structures
1 Structure per 54 SQ Miles

LEGEND

COLOR	BID PACK	# OF PACKAGES	TOTAL BRIDGES	BRIDGES UNDER CONSTRUCTION	BRIDGES COMPLETE
	BID PACK 2	5	40	9	31
	BID PACK 3	6	41	10	31
	BID PACK 4	5	34	6	4
	BID PACK 5	5	40	2	0
	BID PACK 6	6	42	0	0
	BID PACK 7	5	41	0	1
	BID PACK 8	6	43	0	0
	BID PACK 9	6	45	0	0
	BID PACK 10	5	40	0	0
	BID PACK 11	6	45	0	0
	BID PACK 12	6	39	0	0
	BID PACK 13	5	33	0	0
	BID PACK 14	6	45	0	0
	BID PACK 15	3	22	0	0
TOTAL		75	550	27	33


Kansas City Region

4,900 SQ Miles
38 Single Span Precast Concrete
14 Two Span Precast Concrete
43 Three Span Precast Concrete
1 Four Span Precast Concrete
5 Cast in Place Slab/Box Culvert
2 Steel Beam W/ Concrete Deck
1 Pipe
1 SuperCore
109 Total Structures
1 Structure per 47 SQ Miles

Southwest Region

22,389 SQ Miles
40 Single Span Precast Concrete
28 Two Span Precast Concrete
40 Three Span Precast Concrete
7 Four Span Precast Concrete
1 Five Span Precast Concrete
10 Cast in Place Slab/Box Culvert
2 Steel Beam W/ Concrete Deck
128 Total Structures
1 Structure per 175 SQ Miles

SAFE AND SOUND BRIDGE IMPROVEMENT PLAN



Northeast Region

15,057 SQ Miles
42 Single Span Precast Concrete
18 Two Span Precast Concrete
47 Three Span Precast Concrete
3 Four Span Precast Concrete
2 Cast in Place Slab/Box Culvert
2 Steel Beam W/ Concrete Deck
114 Total Structures
1 Structure per 132 SQ Miles

Southeast Region

20,545 SQ Miles
41 Single Span Precast Concrete
15 Two Span Precast Concrete
21 Three Span Precast Concrete
1 Four Span Precast Concrete
12 Cast in Place Slab/Box Culvert
6 Steel Beam W/ Concrete Deck
1 SuperCore
97 Total Structures
1 Structure per 211 SQ Miles

Team Organization/Communications

- Executive Met 3-4 times/year
- Central Daily Calls/Weekly Meetings
- Regional Daily Calls/Weekly Meetings
- Bridge Daily On-Site Coordination
- Specialist Variable – Based on Need



Risk Assignment

MoDOT

- ROW
- Environmental
- Community Relations
- Inspection
- Utilities

KTU

- Design
- Suppliers
- Subcontractors
- Schedule




Safety, Quality, and Speed



K0131 10-18-06
Looking east.



B0001 - Route 98 - Andrew County
West Approach
07-10-2012




KTU's Design Goals



- Practical Design
- Rapid, Repetitive Construction
- Durability
- Minimize Site Impacts
- Efficient Usage of Labor and Materials
- Maximum Usage of Precast Concrete Units





Structural Approach



Additional Applicable Standards (Cored Slabs and Box Beams)

- FHWA Approved
- Allows for Rapid, Repetitive Construction
- Proven Durability in North Carolina, South Carolina, and other states
- A Practical Design for the program's ADT requirements



Structure Types

• Adjacent Core Slab	196
• Adjacent Box Beam	116
• Adjacent CS/BB	45
• Spread Core Slab	80
• Spread Box Beam	41
• Spread CS/BB	23
• Steel Girder	8

• NU Girder	5
• Flat Slab	17
• Box Culvert	15
• Pipe Culvert	1
• Super-cor	1
• Prestressed Slab	3
• Hybrid Composite	3


TOTAL	554
--------------	------------

Pre-Fabricated Materials

- CFM – Contractor-Furnished Materials
- Fabrication off Critical Path
- Pricing/Escalation



Pre-Construction: Site Plan Review



Execution

- Planning Challenges

- Just-in-time design is typical.
- Accelerated pace (10+ bridges/week)
- Average 20+ bridges/month

- Logistical Challenges

- 554 bridges in 111 different counties
- Average distance between bridges – 11 miles
- Avg. construction schedule: 45 calendar days/bridge



Construction Sequence



Demolition of Existing Bridge

Construction Sequence



**Pile Foundations
Used at Most
Sites**

Construction Sequence



End Bent Construction (beams “stacked and stored” on site)

Construction Sequence



Erecting Pre-cast Beams



Construction Sequence



When All the Dust Settles, Missouri Has A New Bridge

Completion Speed

- Average time to complete 42 Days/Bridge
- Completion by Bridge Type:
 - Shortest
 - Box 27 Hours of Traffic Impact
 - Single Span 8 Days
 - Double Span 31 Days
 - Triple Span 28 Days
 - Four Span 33 Days

156 Bridges Complete in 2010

281 Bridges Completed in 2011

117 Bridges Completed in 2012



Project Results



1. GOAL: *Deliver good bridges at a great value.*
 - RESULT: **UNDER BUDGET**
2. GOAL: *Minimize public inconvenience through increased construction speed & flexible schedule.*
 - RESULT: **AVG. CLOSURE – 42 DAYS**
3. GOAL: *Complete by Oct. 31, 2014.*
 - RESULT: **2 years ahead of MoDOT requirement.**
 - RESULT: **14 months ahead of KTU commitment (12/31/13).**

Bridges Completed



Recreational Destinations



Lessons Learned - Procurement

- Confidential Meetings
- Additional Applicable Standards
- Design Exceptions
- Innovation and Thorough Vetting of Issues
- Scoring Spread



Lessons Learned - Design

- Standardization
- Prefabricated Elements/Interchangeable Parts
- Constructability Reviews
- Speed/Volume
- Coordinated with Subcontracting
- Work Together from the Start



Lessons Learned - Construction

- Learn from Early Bridges
- Best Practices Manual – Always Get Better
- Contractor Furnished Materials
- Repetition – Builds Speed and Quality
- Pre-Fabrication - Consistency and Interchangeable Parts
- Flexible Scheduling



Lessons Learned



Best Practices



Big Picture - Lessons Learned

- Build a Team to Build a Project
- Safety and Quality Process and Culture
- Communications, Internal and External
- Issues = Opportunities
- 360 Degree Reviews/Surveys



Design-Build Contract Model

- Procurement Process Flexibility
- Execution Flexibility
- Adaptable To Changes and Innovations
- Manage Risk (Assign or Limit)



Safe & Sound

800 Better Bridges by 2012

