

CHALLENGES OF THE SUPERSTRUCTURE "ÄLVSBACKA BRIDGE"




PETER JACOBSSON MARTINSON TRÄBROAR AB www.martinsons.se



OUTLINE

- What has been built
- Background to the chosen solution
- Assembly method
- Conclusions






WHAT HAS BEEN BUILT?

CABLE STAYED BRIDGE IN TIMBER

- Distance between pylons, span length: 130 m, total length 182 m.
- Free width of decking: 4 m
- Height of pylons: 24 m
- Amount of timber: Approximately 200 ton, 400 m3
- Amount of steel: Approximately 70 ton, 9 m3



- PERFORMED ACCORDING TO THE SWEDISH BRIDGE CODE "BRO 2004"
- DESIGN WORK

 COWI & MARTINSONS





BUILT IN SKELLEFTEÅ CITY 2011, CROSSING THE "SKELLEFTEÅ RIVER"


CLIENT- MUNICIPALITY OF SKELLEFTEÅ





BACKGROUND TO THE BUILT SOLUTION

INITIALLY SUGGESTED DESIGN FROM THE MUNICIPALITY IN COOPERATION WITH A LOCAL ARCHITECT



ADVANTAGES:


- DOES NOT INTRUDE ON THE LANDAREA
- CONSIDERD AS ESTETHICAL AND A GREAT LANDMARK

DISADVANTAGE:

THE COST MUCH HIGHER
THAN THE MUNICIPALITIES
BUDGET



- A NEW EVALUATION PROCESS WITH LESS REQUIREMENTS ON APPEARANCE TOOK PLACE
- IF THE SUPPORT IN THE RIVER COULD BE EXCLUDED A LOT OF THE COST WOULD DISAPPEAR.
- SUGGESTED SOLUTION FROM MARTINSONS AND COWI



THE MUNICIPALITY CHOOSE TO CONTRACT MARTINSONS TO BUILD THIS SOLUTION



- MAIN CHALLENGES
 - ASSEMBLY METHOD
 - DYNAMIC BEHAVIOUR
 - LARGE STATIC FORCES THAT HAD TO BE TAKEN CARE OF
 - PERFORMANCE TO ACHEIVIE A LONG LIFETIME AND PROTECTION AGAINST MOISTURE INFLUENCE.






IDEA OF ASSEMBLING METHOD

CAN THE BRIDGE DECK BE PULLED OUT INSTEAD OF LIFTED OUT?

ERECTING THE PYLONS & LONG BARS
 WITH TRANSVERSE BEAM



- STRETCHING UP THE BAR SYSTEM



PULLING OUT THE BRIDGE DECK PIECES.



 A LOT OF TIME WAS SPENT DURING DESIGN WORK TO MAKE THE METHOD FEASIBLE AND EFFECTIVE



ASSEMBLING METHOD – TWO TEMPORARY CABLES





ASSEMBLING METHOD – PULLING OUT BARS AND TRANSVERSE MID BEAM





ASSEMBLING METHOD – PYLONS TO NORTH BRIDGE SITE ON THEIR WAY..





ASSEMBLING METHOD – PYLONS READY TO BE ERECTED







ASSEMBLING METHOD – PYLONS ON THEIR WAY UP





ASSEMBLING METHOD – PYLONS IN PLACE







ASSEMBLING METHOD – PULLING OUT BARS AND TRANSVERSE BEAMS









ASSEMBLING METHOD – FIRST BRIDGE DECK PIECE ON SITE





ASSEMBLING METHOD – PASSING MIDSPAN





ASSEMBLING METHOD – IN POSITION FOR THE FOURTH BRIDGE DECK





ASSEMBLING METHOD – BRIDGE DECK IN POSITION



COMPLETING THE CONCRETE FOUNDATION

REMAINING WORK FOR 2-3 WEEKS

- ADJUSTMENTS
- PERMANENT LOOKING
- REMOVING TEMPORARY MATERIAL
- INSTALLATIONS
- REAMINING CLADDING





CONCLUSIONS

- The assembly method
 - worked out well and is definitely something we will use again if the opportunity comes up.
 - can be refined to achieve an even more effective method.
 - handled 270 ton material with only a small barge in he river. Can it be don
 without the barge? That's a future challenge we would like to evaluate.
- THE "Älvsbacka" bridge is frequentley used every day and is appreciated of the citizens
 - Very positive response from users dynamic response OK!
 - The client, Municipality of Skellefteå, is very satisfied



THANK YOU FOR YOUR ATTENTION!

