

SUDAS Revision Submittal Form

Status Date: As of 10/26/2018 **Topic:** Dewatering
Manual: Specifications **Manual Location:** Section 3010, 1.08, A, 6

Requested Revision:

1.08 MEASUREMENT AND PAYMENT

A. General: The following items are incidental to the underground utility being installed and will not be paid for separately:

1. Standard trench excavation.
2. Removal and disposal of unsuitable backfill material encountered during standard trench excavation.
3. Removal of abandoned private utilities encountered during trench excavation.
4. Furnishing and placing granular bedding material.
5. Placing and compacting backfill material.
6. Dewatering including, but not limited to, all equipment such as generators, pumps, rock for sump pits, discharge piping, and any extra excavation needed to facilitate dewatering according to stormwater regulations, as applicable.
7. Sheet piling, shoring, and bracing.
8. Adjusting the moisture content of excavated backfill material to the range specified for placement and compaction.
9. Temporary support for existing water, sewer, gas, telephone, electric, and other utilities or services that cross the trench.

Reason for Revision: Clarifying what work activities are encompassed by dewatering.

Comments: Will be added to the Iowa DOT Specifications as well.

District:	<input type="checkbox"/> 1	<input type="checkbox"/> 2	<input type="checkbox"/> 3	<input checked="" type="checkbox"/> 4	<input type="checkbox"/> 5	<input type="checkbox"/> 6
Comments:	None.					
Action:	<input type="checkbox"/> Deferred		<input type="checkbox"/> Not Approved		<input checked="" type="checkbox"/> Approved	
District:	<input type="checkbox"/> 1	<input type="checkbox"/> 2	<input checked="" type="checkbox"/> 3	<input type="checkbox"/> 4	<input type="checkbox"/> 5	<input type="checkbox"/> 6
Comments:	Contractor to supply dewatering plan - Iowa DOT requires it. Add to the submittal item. <i>Note - already included in 1.03.</i>					
Action:	<input type="checkbox"/> Deferred		<input type="checkbox"/> Not Approved		<input checked="" type="checkbox"/> Approved	
District:	<input checked="" type="checkbox"/> 1	<input type="checkbox"/> 2	<input type="checkbox"/> 3	<input type="checkbox"/> 4	<input type="checkbox"/> 5	<input type="checkbox"/> 6
Comments:	None.					
Action:	<input type="checkbox"/> Deferred		<input type="checkbox"/> Not Approved		<input checked="" type="checkbox"/> Approved	
District:	<input type="checkbox"/> 1	<input checked="" type="checkbox"/> 2	<input type="checkbox"/> 3	<input type="checkbox"/> 4	<input type="checkbox"/> 5	<input type="checkbox"/> 6
Comments:	None.					
Action:	<input type="checkbox"/> Deferred		<input type="checkbox"/> Not Approved		<input checked="" type="checkbox"/> Approved	
District:	<input type="checkbox"/> 1	<input type="checkbox"/> 2	<input type="checkbox"/> 3	<input type="checkbox"/> 4	<input type="checkbox"/> 5	<input checked="" type="checkbox"/> 6
Comments:	None.					
Action:	<input type="checkbox"/> Deferred		<input type="checkbox"/> Not Approved		<input checked="" type="checkbox"/> Approved	
District:	<input type="checkbox"/> 1	<input type="checkbox"/> 2	<input type="checkbox"/> 3	<input type="checkbox"/> 4	<input checked="" type="checkbox"/> 5	<input type="checkbox"/> 6
Comments:	Discuss NPDES permit language. Remove wellpoints, sheet piling, and cofferdams from the description. <i>Note - done.</i>					
Action:	<input type="checkbox"/> Deferred		<input type="checkbox"/> Not Approved		<input checked="" type="checkbox"/> Approved	

Final District Action Summary: All 6 districts approved; see comments above.

Board of Directors Action: