

SUDAS Revision Submittal Form

Status Date: As of 5/17/2019 **Topic:** Temporary traffic signals
Manual: Specifications **Manual Location:** 8010, 1.08 and 3.06

Requested Revision:

1.08 MEASUREMENT AND PAYMENT

A. Traffic Signal:

1. **Measurement:** Lump sum item; no measurement will be made.
2. **Payment:** Payment will be at the lump sum price for traffic signal installation.

B. Temporary Traffic Signal:

1. **Measurement:** Lump sum item; no measurement will be made.
2. **Payment:** Payment will be at the lump sum price for temporary traffic signal. 50% of the lump sum bid amount will be paid upon completion of the installation and successful initial operation of the signal; the final 50% will be paid upon removal of the temporary traffic signal and cleanup of the site.
3. **Includes:** Lump sum price includes but is not limited to furnishing, installation, maintenance, and removal of poles, wiring, traffic signal control equipment including pedestrian equipment if specified, and all appurtenances.

....

3.06 TEMPORARY TRAFFIC SIGNAL

Construct according to Figure 8010.107 and to the configuration specified in the contract documents. Remove the temporary traffic signal as directed by the Engineer.

Reason for Revision: Expanded payment and removal process for temporary traffic signals.

Comments: None.

District:	<input type="checkbox"/> 1	<input type="checkbox"/> 2	<input type="checkbox"/> 3	<input checked="" type="checkbox"/> 4	<input type="checkbox"/> 5	<input type="checkbox"/> 6
Initial Comments:	None.					
Final Comments:	None.					
Action:	<input type="checkbox"/> Deferred		<input type="checkbox"/> Not Approved		<input checked="" type="checkbox"/> Approved	
District:	<input type="checkbox"/> 1	<input type="checkbox"/> 2	<input checked="" type="checkbox"/> 3	<input type="checkbox"/> 4	<input type="checkbox"/> 5	<input type="checkbox"/> 6
Initial Comments:	None.					
Final Comments:	None.					
Action:	<input type="checkbox"/> Deferred		<input type="checkbox"/> Not Approved		<input checked="" type="checkbox"/> Approved	
District:	<input checked="" type="checkbox"/> 1	<input type="checkbox"/> 2	<input type="checkbox"/> 3	<input type="checkbox"/> 4	<input type="checkbox"/> 5	<input type="checkbox"/> 6
Initial Comments:	None.					
Final Comments:	None.					
Action:	<input type="checkbox"/> Deferred		<input type="checkbox"/> Not Approved		<input checked="" type="checkbox"/> Approved	
District:	<input type="checkbox"/> 1	<input checked="" type="checkbox"/> 2	<input type="checkbox"/> 3	<input type="checkbox"/> 4	<input type="checkbox"/> 5	<input type="checkbox"/> 6
Initial Comments:	Pay 50% at installation and 50% at removal. <i>Note - done.</i>					
Final Comments:	None.					
Action:	<input type="checkbox"/> Deferred		<input type="checkbox"/> Not Approved		<input checked="" type="checkbox"/> Approved	
District:	<input type="checkbox"/> 1	<input type="checkbox"/> 2	<input type="checkbox"/> 3	<input type="checkbox"/> 4	<input type="checkbox"/> 5	<input checked="" type="checkbox"/> 6
Initial Comments:	Pay 50% at installation and 50% at removal. Includes maintenance. In the bid item list in the Design Manual, maybe include ____ (location) to help the designers understand that the bid item should be set up at each location. <i>Note - first two items are done; last item will be considered.</i>					
Final Comments:	Request for next time - timing of setup (timing adjustment if specified). Staging plan. Separate bid item for subsequent adjustments beyond additional setup and tear down.					
Action:	<input type="checkbox"/> Deferred		<input type="checkbox"/> Not Approved		<input checked="" type="checkbox"/> Approved	
District:	<input type="checkbox"/> 1	<input type="checkbox"/> 2	<input type="checkbox"/> 3	<input type="checkbox"/> 4	<input checked="" type="checkbox"/> 5	<input type="checkbox"/> 6
Initial Comments:	Pay 50% at installation and 50% at removal. <i>Note - done.</i>					
Final Comments:	None.					
Action:	<input type="checkbox"/> Deferred		<input type="checkbox"/> Not Approved		<input checked="" type="checkbox"/> Approved	

Final District Action Summary: All 6 districts approved; see comments above.

Board of Directors Action: Approved.